


City of Bryan

MLK SIDEWALK AND STREETSCAPING


Phase I & II

City Job No. 350-D8-0828
JC Job No. C0011-005



* DRAWING INDEX *


DESCRIPTION	DRAWING NO.
GENERAL	
GENERAL LOCATION 1.....	G1
GENERAL LOCATION 2.....	G2
SIDEWALK AND STREETSCAPING	
00+00 - 15+00	C1
15+00 - 30+00	C2
30+00 - 45+00	C3
45+00 - 60+00	C4
60+00 - 75+00	C5
75+00 - 90+00	C6
90+00 - 105+00	C7
105+00 - 120+00	C8
120+00 - 135+00	C9
135+00 - 150+00	C10
SITE DETAILS	
PROJECT DETAILS 1.....	SD1
PROJECT DETAILS 2.....	SD2
PEDESTRIAN BRIDGE.....	SD3
PLANTING PLAN - CARVER SCHOOL ENTRANCE.....	LS1
BCS STANDARD DETAILS	
STREET.....	ST
SIDEWALK	SW
DRAINAGE	D
SWPP	SWPP
TXDOT STANDARD DETAILS	
MAILBOX MOUNTING AND SPACING	HB-06(1) 1 OF 3
MAILBOX BRACKET CONNECTING DETAILS.....	HB-06(1)-2 OF 3
MAILBOX SUPPORT/FOUNDATION	HB-06(1)-3 OF 3



CITY OF BRYAN
The Good Life, Texas Style.




City Council:
SMD 1-Al Saenz
SMD 2-Paul Madison, Sr.
SMD 3-Jason Bienski
(Mayor Pro-Tem)
SMD 4-Ann Horton
SMD 5-Art Hughes
P6AL-Mike Southerland

Mayor:
D. Mark Conlee
City Manager:
David Watkins
City Engineer:
W. Paul Kaspar, P.E.



THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009

JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000



- PROJECT SPECIFIC NOTES:**
1. CONSTRUCTION STAKING TO BE PROVIDED BY THE CONTRACTOR.
 2. NO POTHOLING OF UTILITIES WAS DONE ON SITE.
 3. THE PROJECT AREA IS PARTIALLY LOCATED IN A DEFINED 100-YEAR FLOOD PLAIN AS PER F.I.R.M. COMMUNITY PANEL 4804100133C, BRAZOS COUNTY, TEXAS INCORPORATED AREA EFFECTIVE JULY2, 1992. FLOOD ELEVATIONS NOTED ON DRAWING ARE FROM REFERENCED MAP.
 4. CONTRACTOR IS RESPONSIBLE FOR NOTIFYING PROPERTY OWNERS IN ADVANCE OF WORK PERFORMED ON OR ADJACENT TO THEIR PROPERTY.
 5. CONTRACTOR TO FIELD VERIFY ACTUAL SLOPES OF EXISTING DRIVEWAYS AND COORDINATE FINAL LENGTHS, ETC.
 6. SPECIFIC HEIGHT OF INDIVIDUAL RETAINING WALLS TO BE DIRECTED BY CITY OF BRYAN INSPECTOR.
 7. CONTRACTOR TO FURNISH AND INSTALL CEMENT STABILIZED SAND BASE AS DIRECTED BY CITY OF BRYAN INSPECTOR FOR CURB, SIDEWALK, ETC.
 8. CONTRACTOR IS ALLOWED TO OPERATE EQUIPMENT ON PARK AREAS, PROPERTY MUST BE RETURNED TO EXISTING STATE.
 9. CONTRACTOR TO RETURN ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITION, AS DIRECTED BY, AND TO THE SATISFACTION OF THE CITY OF BRYAN INSPECTOR. THIS WORK WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED SUBSIDIARY TO THE VARIOUS BID ITEMS.
 10. ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN DISTURBED BY CONSTRUCTION SHALL BE ADEQUATELY BLOCK SODDED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED, BEGINNING WITHIN FOURTEEN (14) CALENDAR DAYS OF LAST DISTURBANCE
 11. BLACK SOD FROM STA 0+00 TO 17+00, HYDROMULCH THE REMAINING.
 12. APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN DISTURBED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.
 13. ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.
 14. TRAFFIC CONTROL TO BE IN ACCORDANCE TO THE CITY OF BRYAN STANDARDS.
 15. CITY TO PROVIDE TEMPORARY CONSTRUCTION EASEMENTS WHERE APPLICABLE
 16. PHONE CONTACTS FOR VARIOUS PARTIES WHO WILL BE INVOLVED WITH THIS PROJECT ARE AS FOLLOWS:
JONES & CARTER, INC., STEVE DUNCAN 978-731-8000
CITY OF BRYAN ENGINEERING BARNEY WILLIAMS 979-209-5030,
JAYSON BARNHART 979-209-5800
BTU, 821-5830/5786/5793
AMOS GAS KIMBERLY WINN 979-774-2506
QUEST COMMUNICATIONS 800-283-4257
UTLIQUEST 281-589-6450 OTHER POWER POLE UTILITIES.
USPS, SHERRY BRIDGES (979) 774-2318

City of Bryan
City Project No. 350-D8-0828

**MLK Sidewalk and Streetscaping
Phase 1 & 2**




General Location 1

JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: CLS
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --

THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009

SHEET NO.
G1
OF 2



GENERAL NOTES:

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SECURITY AND SAFETY PROVISIONS REQUIRED TO PROTECT INDIVIDUALS, EQUIPMENT, MATERIALS, AND WORKMANSHIP NECESSARY FOR THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STORAGE OF MATERIALS IN A SAFE AND WORKMANLIKE MANNER TO PREVENT INJURIES, DURING AND AFTER WORKING HOURS, UNTIL PROJECT COMPLETION.
2. THE CONTRACTOR SHALL ADVISE THE ENGINEER OF ANY APPARENT OR SPECIAL NEEDS TO COMPLETE THE SCOPE OF WORK INCLUDED IN THIS PROJECT. THESE MAY INCLUDE THE NEED FOR OWNER PROVIDED SERVICES SUCH AS WATER, STAFF AVAILABILITY, ETC.
3. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 48 HOURS PRIOR TO COMMENCEMENT OF WORK.
4. THE CONTRACTOR SHALL PROVIDE A DETAILED WRITTEN SCHEDULE WHICH OUTLINES A LOGICAL, ORDERLY PLAN FOR COMPLETING THE WORK REQUIRED FOR THIS PROJECT. THIS SCHEDULE SHALL SPECIFY DATES AND TIME INCREMENTS FOR THE VARIOUS ITEMS OF WORK TO MEET THE CONTRACT PERIOD. THROUGHOUT THE DURATION OF THE CONTRACT PERIOD, THE CONTRACTOR SHALL MAINTAIN CLOSE COORDINATION WITH THE OWNER AND ENGINEER REGARDING SCHEDULING AND PROGRESS OF THE PROJECT.
5. THE CONTRACTOR SHALL MAKE EVERY EFFORT TO MAINTAIN ACCESS DURING THE CONSTRUCTION PERIOD. SCHEDULING OF ACTIVITIES SHOULD EMPHASIZE ACCESSIBILITY TO THE PROJECT SITE. EXTENDED PERIODS OF RESTRICTED ACCESS MUST BE LIMITED.
6. THE CONTRACTOR SHALL DISPOSE OF ALL EXCESS EXCAVATION, CONCRETE AND OTHER EXCAVATED MATERIALS OFF SITE IN A LEGAL MANNER.
7. THE CONTRACTOR SHALL PERFORM ALL CLEARING AND GRUBBING OPERATIONS REQUIRED TO INSTALL THE IMPROVEMENTS COVERED UNDER THIS PROJECT AND THE COSTS THEREOF SHALL BE INCLUDED IN THE UNIT PRICES OF APPROPRIATE ITEMS IN THE PROPOSAL.
8. CONTRACTOR SHALL PROTECT EXISTING MONUMENTS, YARDS, PRIVATE UTILITIES, DRIVES, CURBS, MAIL BOXES, SIGNS, IMPROVEMENTS, CULVERTS, AND OWNER'S FACILITIES FROM DAMAGE DURING CONSTRUCTION. DAMAGE DONE TO THESE ITEMS SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE. THE CONTRACTOR SHALL MOVE AND REPLACE SUCH MOVABLE ITEMS AS MAIL BOXES, TRAFFIC CONTROL, BUSINESS SIGNS, AND STREET SIGNS AS NECESSARY FOR CONSTRUCTION. FENCES OR STRUCTURES WHICH REQUIRE DISMANTLING OR REMOVAL SHALL BE RECONSTRUCTED OR REPLACED TO EQUAL OR BETTER THAN ORIGINAL CONDITION (SUBSIDIARY).
9. AT THE END OF ALL CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL RESTORE EXISTING FACILITY (I.E. PROPERTY) EQUAL TO OR BETTER THAN EXISTING SITE CONDITIONS PRIOR TO CONSTRUCTION. CLEAN-UP ACTIVITIES SHALL BE MAINTAINED THROUGHOUT THE CONTRACT PERIOD.
10. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO INSURE THAT SURFACE DRAINAGE IS NOT IMPEDED BY CONSTRUCTION WORK.
11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND PROTECTION OF CONSTRUCTION ACTIVITIES DURING THE CONTRACT PERIOD. THIS SHALL INCLUDE ANY EROSION CONTROL MEASURES AND REGRADING NECESSARY TO ACHIEVE THE LINES AND GRADES SET FORTH BY THESE PLANS.

11. SIGNING, BARRICADING AND LIGHTING FOR CONSTRUCTION WITHIN ROAD RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND OTHER APPLICABLE STATE OR LOCAL STANDARDS. SIGNS, BARRICADES AND LIGHTS SHALL BE KEPT CLEAN, OPERATIONAL AND PROPERLY POSITIONED TO ASSURE PROPER SAFETY PRECAUTIONS.
12. THE CONTRACTOR SHOULD BE AWARE THAT THERE ARE OVERHEAD AND UNDERGROUND ELECTRICAL, TELEPHONE, ETC. LINES WITHIN THE PROJECT SITE. THE CONTRACTOR AND HIS PERSONNEL SHALL EXERCISE CARE AROUND THESE LINES TO PREVENT DAMAGE TO LINES AND INJURY TO THE PERSONNEL. ANY DAMAGE SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE.
13. THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES WITH FACILITIES IN THE PROJECT LOCATION NOT LESS THAN 48 HOURS PRIOR TO CONSTRUCTION ACTIVITIES IN THE RESPECTIVE WORK AREAS. ADEQUATE PROVISIONS FOR PROTECTING EXISTING FACILITIES SHOULD BE EMPLOYED.
14. ALL EXISTING UTILITY LINES, DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
15. THE LOADING AND UNLOADING OF ALL MATERIALS AND EQUIPMENT SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDED PRACTICES AND SHALL AT ALL TIMES BE PERFORMED WITH CARE TO AVOID ANY DAMAGE TO THE MATERIAL. THE CONTRACTOR SHALL LOCATE AND PROVIDE THE NECESSARY STORAGE AREAS FOR MATERIALS AND EQUIPMENT.
16. ALL MATERIALS AND EQUIPMENT SHALL BE BOTH FURNISHED AND INSTALLED UNLESS OTHERWISE NOTED.
17. CONTRACTOR SHALL PROVIDE SHEETING, SHORING AND BRACING AS NECESSARY TO PROTECT WORKMEN AND EXISTING UTILITIES DURING ALL PHASES OF CONSTRUCTION AS PER O.S.H.A. REQUIREMENTS.
18. EXCAVATIONS, DISTURBED AREAS, AND TRENCH LINES SHALL BE FINISH GRADED AND HYDROMULCH SEEDED AFTER COMPLETION.
19. NSP = NO SEPARATE PAY ITEM IN THE BID PROPOSAL. ITEMS SHALL BE CONSIDERED SUBSIDIARY TO THE LISTED PAY ITEMS. ALL MATERIAL AND LABOR NOT IDENTIFIED AS A SEPARATE BID ITEM SHALL BE CONSIDERED SUBSIDIARY TO THE ITEM IN WHICH IT IS USED.
20. ALL WORK SHALL COMPLY WITH CITY AND BCS UNIFIED DESIGN STANDARDS.

BENCHMARK NOTES:

1. ALL ELEVATIONS ARE BASED ON THE CITY OF BRYAN CONTROL MONUMENT SYSTEM, GPS MONUMENT #35, ELEVATION=331.46 FEET (NAVD88 DATUM).
2. TBM #1 IS A RR SPIKE SET IN 24" OAK TREE IN THE NORTHWEST RIGHT-OF-WAY OF EAST MLK STREET, APPROX. 200 FEET SOUTHWEST FROM THE SOUTHWEST EDGE OF EARL RUDDER FREEWAY, AND APPROX. 12 FEET NORTHEAST OF CONCRETE DRIVEWAY TO THE CHURCH AT 2240 EAST MLK. ELEVATION 309.05 FEET.
3. TBM #2 IS A RR SPIKE IN A POWER POLE IN THE NORTHWEST RIGHT-OF-WAY OF EAST MLK STREET, APPROX. 275 FEET NORTHEAST OF THE CENTERLINE OF DUMAS STREET. ELEVATION 308.48 FEET
4. TBM #3 IS A RR SPIKE IN A POWER POLE IN THE NORTHWEST RIGHT-OF-WAY OF EAST MLK STREET APPROX. 315 FEET NORTHEAST OF THE INTERSECTION OF DUMAS STREET AND EAST MLK STREET. ELEVATION 310.54 FEET.
5. TBM #4 IS A RR SPIKE IN A POWER POLE IN THE NORTHWEST CORNER OF THE INTERSECTION OF MIDDLE STREET AND EAST MLK STREET. ELEVATION 327.43 FEET
6. TBM #5 IS A RR SPIKE IN A POWER POLE IN THE NORTHWEST CORNER OF THE INTERSECTION OF MIDDLE STREET AND EAST MLK STREET. ELEVATION 327.43 FEET
7. TBM #6 IS A RR SPIKE IN A POWER POLE 5.2 FEET FROM THE BACK OF CURB ON THE NORTHWEST SIDE OF EAST MLK STREET IN THE SOUTHWEST CORNER OF THE INTERSECTION OF CAROLINE STREET (NOT BUILT) AND EAST MLK STREET. ELEVATION 334.43 FEET.
8. TBM #7 IS A RR SPIKE IN A POWER POLE ON THE NORTH SIDE OF MLK STREET AT THE INTERSECTION OF EAST MLK STREET AND PIERCE STREET, APPROX. 9 FEET FROM THE BACK OF CURB. ELEVATION 338.25 FEET.
9. TBM #8 IS A RR SPIKE IN A POWER POLE IN THE NORTH RIGHT-OF-WAY OF EAST MLK STREET, APPROX. 91 FEET WEST OF THE OF THE CENTERLINE OF NORTH HOUSTON STREET, AND APPROX. 6.5 FEET NORTH OF THE BACK OF CURB. ELEVATION 357.08 FEET.
10. TBM #9 IS A RR SPIKE IN A POWER POLE ON THE SOUTHWEST CORNER OF TABOR AVENUE AND EAST MLK STREET APPROX. 47.50 FEET WEST OF THE CENTERLINE OF TABOR AVENUE. ELEVATION 359.49 FEET.



SURVEY GENERAL NOTES:

1. THIS SURVEY WAS BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM CENTRAL ZONE (NAD83), REFERENCED TO CITY OF BRYAN CONTROL MONUMENT SYSTEM, MONUMENTS GPS-35 AND GPS-16. THE SURFACE COORDINATE TO GRID COORDINATE SCALE FACTOR FOR THIS PROJECT IS: 0.99988635.
2. THIS IS NOT A BOUNDARY OR RIGHT-OF-WAY SURVEY. STREET RIGHTS-OF-WAY SHOWN ARE BASED ON RECORD INSTRUMENTS, PLATS, RIGHT-OF-WAY INFORMATION PROVIDED BY THE CITY OF BRYAN, AND FOUND MONUMENTATION BASED ON A LIMITED SEARCH UNDER THE SCOPE OF THIS PROJECT. THE RIGHTS-OF-WAY SHOWN SHOULD BE USED FOR ORIENTATION ONLY. OUTSIDE OF THE INFORMATION NOTED, NO ADDITIONAL RESEARCH OF THE PUBLIC RECORDS OF BRAZOS COUNTY, TEXAS REGARDING FOR EASEMENTS OR ENCUMBRANCES WAS PERFORMED BY JONES & CARTER, INC.
3. THIS SURVEY DOES NOT PROVIDE ANY DETERMINATION CONCERNING WETLANDS, FAULT LINES, TOXIC WASTE OR ANY OTHER ENVIRONMENTAL ISSUES SUCH MATTERS SHOULD BE DIRECTED BY THE CLIENT OR PROSPECTIVE PURCHASER TO AN EXPERT CONSULTANT.
4. ACCORDING TO COMMUNITY PANEL NO. 48041C0133 C OF THE FEDERAL EMERGENCY MANAGEMENT AGENCY'S FLOOD INSURANCE RATE MAPS FOR THE CITY OF BRYAN, BRAZOS COUNTY, TEXAS UNINCORPORATED AREA, EFFECTIVE DATE JULY 2, 1992, A PORTION OF THE SUBJECT TRACT IS SITUATED WITHIN ZONE "AE" DEFINED AS BASE FLOOD ELEVATIONS DETERMINED, AND WITHIN SHADED ZONE "X", DEFINED AS AREAS OF 500 YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD AND THE REMAINDER OF THE SUBJECT TRACT IS SITUATED WITHIN UNSHADED ZONE "X"; DEFINED AS AREAS DETERMINED TO BE OUTSIDE THE 100-YEAR FLOOD PLAN. THIS FLOOD STATEMENT DOES NOT IMPLY THAT THE PROPERTY OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS FLOODS CAN AND WILL OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOOD STATEMENT SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.
5. THE SURVEYOR HAS NOT BEEN PROVIDED WITH CONSTRUCTION PLANS SHOWING THE LOCATION OF UNDERGROUND UTILITIES. UNDERGROUND UTILITIES MAY EXIST WHICH ARE NOT SHOWN HEREON.
6. VISIBLE IMPROVEMENTS/UTILITIES WERE LOCATED WITH THIS SURVEY; NO SUBSURFACE PROBING, EXCAVATION OR EXPLORATION WAS PERFORMED FOR THIS SURVEY. DIG TEST WAS NOTIFIED AND ANY MARKINGS/LOCATIONS OF UNDERGROUND UTILITIES AS A RESULT OF THAT NOTIFICATION IS SHOWN. THE SURVEYOR MAKES NO GUARANTEES THAT ALL UNDERGROUND UTILITY COMPANIES RESPONDED OR COMPLETELY MARKED THEIR FACILITIES.
7. NO SURVEY WORK WAS PERFORMED ON PROPERTIES LOCATED BETWEEN NORTH TABOR AVENUE AND THE PROJECT LIMITS, NORTHWEST OF KEMP ELEMENTARY SCHOOL.
8. SURVEY WORK WAS PERFORMED ON PROPERTIES LOCATED BETWEEN NORTH TABOR AVENUE, AND WEST EARL RUDDER FREEWAY.
9. A SURVEY WAS NOT PERFORMED FOR ALL AREAS OF THIS PROJECT. THE SIDEWALK SHOULD MATCH THE EXISTING GRADE AS CLOSELY AS POSSIBLE.

City of Bryan
City Project No. 350-D8-0828

**MLK Sidewalk and Streetscaping
Phase 1 & 2**



General Location 2



SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: CLS
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --





SHEET NO.
62
OF 2



DRIVE	EXISTING			PROPOSED		
	SLOPE (%)	LENGTH	SLOPE (%)	Demo Length	Proposed slope	
2A	3.80%	10	8.40%	9	7.40%	
2A-A	17.30%	4	3.20%	15	13.92%	
2A-B	16.30%	4	3.20%	12	13.02%	
2A-C	14.80%	4	2.10%	10	14.81%	
2A-D	4.80%	13.5	0.50%	10	12.75%	
2A-E	7.10%	4	11.00%	10	14.41%	
2A-F	3.00%	6	9.70%	10	8.14%	
2B	-3.40%	7.8	-5.70%	20	-7.72%	
2C	9.10%	4	0.40%	10	6.66%	
2D	19.20%	4	6.10%	15	14.55%	
2E	14.20%	3	1.30%	10	9.83%	
2F	9.60%	19.76	8.20%	20	12.82%	
2G	5.60%			10	11.00%	
2I	5.70%			10	11.25%	

DRIVE	EXISTING			PROPOSED		
	SLOPE (%)	LENGTH	SLOPE (%)	Demo Length	Proposed slope	
2J	9.40%	8	5.20%	15	10.03%	
2K	9.20%	4	8.30%	3	0.60%	
2L	23.60%	4	8.30%			
2M	12.70%	4	1.80%			
2N	14.50%	13.5	2.20%			
2P	15.00%	4	0.50%			
2Q	15.00%	10	7.40%	8	5.30%	
2R	9.90%	20	5.70%			
2S	16.10%	4	0.80%			
2T	16.10%	10	4.50%			
2U	18.00%	10	8.90%			
2V	12.40%	15	4.80%			
2W	6.00%	12	0.80%			
2X	8.50%	12	1.80%			
2Y	10.60%	15	4.50%			
2Z	10.00%	12	3.10%			



City of Bryan
City Project No. 350-D8-0828

MLK Sidewalk and Streetscaping
Phase 1 & 2

15+00-30+00



JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --

THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009

SHEET NO.
C2
OF 10


S:\0-JOB\0011 Bryan-City\0011-005 MLK Sidewalk\DWG\3 SHEET - MLK_recover000.dwg Jun 04 2009 9:43am JGA




CONTRACTOR TO FIELD VERIFY EXISTING DRIVEWAY GRADES W/ CITY INSPECTOR PRIOR TO CONSTRUCTION

06/03/2009 ORIGINAL DESIGN

06/22/2009 CURB RAMP REDESIGN



DRIVE	EXISTING			PROPOSED		
	SLOPE (%)	LENGTH		SLOPE (%)	LENGTH	
3-A	2.00%	4	7.00%			10 6.00%
3-B	3.60%	9.5				10 9.50%
3-C	14.70%	4	15.80%			9.5 4.76%
3-D	12.00%	4	24.40%	10	6.90%	30 17.76%
3-E	15.70%	4	15.90%	13	2.70%	20 20.02%
3-F	17.30%	4	15.80%	15		22 15.12%
3-G	9.70%	4	18.40%	15		23 19.02%
3-H	10.90%	4	11.40%			19 20.46%
3-I	14.00%	4	0.40%			30 13.67%
3-K	5.30%	10	1.00%			10 11.47%
3-L	16.00%	4	0.90%			10 7.49%
3-M	10.90%	4	-2.30%			10 14.16%
3-N	9.50%	4	6.30%			10 4.37%
3-O	10.40%	4	-1.70%			10 11.29%
3-P	6.20%	4	15.60%	7		10 4.75%
3-Q	3.10%	18				11 18.01%
3-R	2.50%					10 4.75%
3-S	13.60%	4	19.10%			10 3.25%
3-T						30 20.89%



City of Bryan
City Project No. 350-D8-0828

MLK Sidewalk and Streetscaping
Phase 1 & 2



30+00-45+00

JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr., East, Ste. 110C, College Station, Texas 77840 (979) 731-8000



SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --

THIS SEAL WAS AUTHORIZED BY
STEVE E. DUNCAN
P.E. 83252
ON 06/22/2009

SHEET NO.
C3
OF 10



06/03/2009 ORIGINAL DESIGN
06/22/2009 CURB RAMP REDESIGN



City of Bryan
City Project No. 350-D8-0828
MLK Sidewalk and Streetscaping
Phase 1 & 2
45+00-60+00



JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr., East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --




THIS SEAL WAS AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/22/2009

SHEET NO.
C4
OF 10

DRIVE	EXISTING			PROPOSED		
	SLOPE (%)	LENGTH	SLOPE (%)	LENGTH	Demo Length	Proposed slope
5-A	15.00%	0			30	18.25%
5-B	4.50%	18			10	8.25%
5-C	10.80%	5	0.52%	19.3	10	11.07%
5-D	14.67%	4.5	0.63%	16	10	14.19%
5-E	7.75%	4	11.64%	11	15	10.55%
5-F	13.25%	4	-0.17%	6	10	9.88%
5-G	3.50%	9.7	2.50%	6.7	10	5.67%
5-H	6.70%	19.65	7.00%	10.85	15	9.66%




CONTRACTOR TO FIELD VERIFY
EXISTING DRIVEWAY GRADES
W/ CITY INSPECTOR
PRIOR TO CONSTRUCTION



City of Bryan
City Project No. 350-D8-0828
MLK Sidewalk and Streetscaping
Phase 1 & 2
60+00-75+00



JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --




SHEET NO.
C5
OF 10

S:\0-JOB\C0011-Bryan-City\0011-005 MLK Sidewalk\DWG3\SHEET - MLK_recover000.dwg Jun 04 2009 9:45am bja



		EXISTING				PROPOSED	
		PART 1		PART 2		Demo	Proposed
DRIVE	SLOPE (%)	LENGTH	SLOPE (%)	LENGTH	Length	slope	
6-A	9.57%	4.7	4.6%	16	10	14.43%	
6-B	9.78%	4.5	11.21%	2.23	10	23.42%	
6-C	9.64%	5.5	9.43%	17.4	20	12.69%	
6-D	9.02%	5.1	1.17%	12	10	9.89%	
6-E	8.94%	4.7	1.12%	9.8	10	8.95%	

CONTRACTOR TO FIELD VERIFY
EXISTING DRIVEWAY GRADES
W/ CITY INSPECTOR
PRIOR TO CONSTRUCTION



City of Bryan
City Project No. 350-D8-0828

MLK Sidewalk and Streetscaping
Phase 1 & 2

75+00-90+00

JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000



SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --





THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009

SHEET NO.
C6
OF 10

DRIVE	EXISTING						PROPOSED		
	PART 1 SLOPE (%)	PART 1 LENGTH	PART 2 SLOPE (%)	PART 2 LENGTH	PART 3 SLOPE (%)	PART 3 LENGTH	Sidewalk width	Demo Length	Proposed slope
7-A	11.51%	5.3	6.19%	11.3			4	10	13.66%
7-B	0.23%	4.26	4.29%	14			4	10	2.93%
7-C	9.60%	4	20.00%	10	3.00%	4	6	18	19.56%
7-D	10.50%	4	7.00%	15			6	15	11.88%
7-E									
7-F									
7-G	14.25%	4	30.09%	4.42	7.04%	9.95	4	23	14.73%
7-H	2.20%	5	-3.42%	3.8	-2.57%	10.5	6	6	-
7-I	11.80%	4	14.20%	10			6	30	16.85%
7-J									
7-K	13.61%	3.16	5.35%	20			4	10	11.89%
7-L	8.25%	5.7	4.25%	15.3	4.60%	4	6	10	12.33%



CONTRACTOR TO FIELD VERIFY
EXISTING DRIVEWAY GRADES
W/ CITY INSPECTOR
PRIOR TO CONSTRUCTION




City of Bryan
City Project No. 350-D8-0828

MLK Sidewalk and Streetscaping
Phase 1 & 2

90+00-105+00

JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr., East, Ste. 110C, College Station, Texas 77840 (979) 731-8000



SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --




THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN
P.E. 83252
ON 06/03/2009

SHEET NO.
C7
OF 10

S:\0-JOB\0011-Bryan-City\0011-005 MLK Sidewalk\DWG3\SHEET - MLK_recover00.dwg Jun 04 2019 9:47am Bg



CONTRACTOR TO FIELD VERIFY
EXISTING DRIVEWAY GRADES
W/ CITY INSPECTOR
PRIOR TO CONSTRUCTION



City of Bryan
City Project No. 350-D8-0828

MLK Sidewalk and Streetscaping
Phase 1 & 2





105+00-120+00

JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --

THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009

SHEET NO.
C8
OF 10




City of Bryan
City Project No. 350-D8-0828

MLK Sidewalk and Streetscaping
Phase 1 & 2

120+00-135+00


JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE:	AS SHOWN	DGN. BY:	SED
DATE:	AS SHOWN	DWN. BY:	JGA
JOB NO.:	C0011-005	DWG. NO.:	--
SUBMITTED:	--	SURV. BY:	--



THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009

SHEET NO.
C9
OF 10



City of Bryan
City Project No. 350-D8-0828

MLK Sidewalk and Streetscaping
Phase 1 & 2

135+00-150+00


JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE: AS SHOWN DGN. BY: SED
DATE: AS SHOWN DWN. BY: JGA
JOB NO. C0011-005 DWG. NO. --
SUBMITTED: -- SURV. BY: --

THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009


SHEET NO.
C10
OF 10

S:\0-000\0001\0001-005 MLK Sidewalk\DWGS\SHEETS-DETAILS.dwg Jun 04/2009 - 9:59am R2




TYPICAL RAMP @ STREET INTERSECTION
WITH EX. STORM INLET
NTS

SEE BCS STANDARDS
FOR SW4-00
WITH FOLLOWING
CHANGES




PAVER DIAMOND PATTERN
NTS




RETAINING WALL
NTS

INVERSE WALK AND DRIVE
THICKNESS TO 6" & PROVIDE
4" OF CEMENT STABILIZED
SAND BASE FOR COMMERCIAL
DRIVES OR STREETS

FIELD VERIFY EXISTING DRIVEWAY GRADE.
REFER TO GRADE CHART TO DETERMINE PROPOSED
GRADE OF CONCRETE.




PROFILE
TYPICAL RESIDENTIAL DRIVEWAY
NTS




SINGLE MAILBOX MOUNT PLAN VIEW
NTS

PAVERS TO BE IN
ACCORDANCE WITH B/CS
STANDARD SW1-02



CURB WALL
NTS

INVERSE WALK AND DRIVE
THICKNESS TO 6" & PROVIDE
4" OF CEMENT STABILIZED
SAND BASE FOR COMMERCIAL
DRIVES OR STREETS



SECTION VIEW: MAILBOX & PAVER DETAIL
NTS


REFER TO TXDOT SHEET
MB-06(1) 3/4 FOR
DETAILS OF APPROVED
FOUNDATION, POST,
PARTS & DETAILS

* NOTE ON DHT
SEE TABLE OF
APPLICABLE DHT NUMBER
ON TXDOT SHEET
MB-06(1), FOR DHT
DESCRIPTION

City of Bryan
City Project No. 350-D8-0828
MLK Sidewalk and Streetscaping
Phase 1 & 2
PROJECT DETAILS 1


JC JONES & CARTER, INC.
ENGINEERS • PLANNERS • SURVEYORS
Texas Board of Professional Engineers Registration No. F-439
700 University Dr., East, Ste. 110C, College Station, Texas 77840 (979) 731-8000

SCALE: AS NOTED DGN. BY: SED
DATE: AS SHOWN DWN. BY: CLS
JOB NO.: C0011-005 DWG. NO.: --
SUBMITTED: -- SURV. BY: --





THIS SEAL WAS
AUTHORIZED BY
STEVE E. DUNCAN,
P.E. 83252
ON 06/03/2009

SHEET NO.
SD1
OF 3




SIDEWALK WITH NO CURB
NTS





**SIDEWALK WITH RETAINING WALL
(HEIGHT VARIES MIN 12" - MAX 48")
AT DRIVEWAY AND RETURN**
NTS


ANGLED RETAINING WALL LENGTH INCLUDED IN LINEAR FOOT BID ITEM. AREAS UNDER 12" CAN FOLLOW CURB WALL DETAIL





**SIDEWALK WITH 4" TO 12" CURB WALL
AND DRIVEWAY RETURN**
NTS



City of Bryan City Project No. 350-D8-0828			
MLK Sidewalk and Streetscaping Phase 1 & 2			
PROJECT DETAILS 2			
JC JONES & CARTER, INC. ENGINEERS • PLANNERS • SURVEYORS Texas Board of Professional Engineers Registration No. F-439 700 University Dr. East, Ste. 110C, College Station, Texas 77840 (979) 731-8000			
SCALE: AS NOTED	DGN. BY: SED		
DATE: AS SHOWN	DWN. BY: CLS		
JOB NO. C0011-005	DWG. NO. --		
SUBMITTED: --	SURV. BY: --		
		THIS SEAL WAS AUTHORIZED BY STEVE E. DUNCAN, P.E. 83252 ON 06/03/2009	
		SHEET NO. SD2 OF 3	





PROFILE
SCALE 1"=50'



ABUTMENT DETAIL

NTS

S:\0-108\c0011 Br-con-City\c0011-005 MIK Sidewalks\DWG\SHEET - BRIDGE.dwg Jun 04 2009 - 8:28am jca

<p>City of Bryan City Project No. 350-D8-0828</p>	
<p>MLK Sidewalk and Streetscaping Phase 1 & 2</p>	
<p>PEDESTRIAN BRIDGE</p>	
 <p>JONES & CARTER, INC. ENGINEERS • PLANNERS • SURVEYORS <i>Texas Board of Professional Engineers Registration No. F-439</i> 700 University Dr., East, Ste. 1100, College Station, Texas 77840 (979) 731-8000</p>	
SCALE: AS SHOWN	DGN. BY: <u>SED</u>
DATE: AS SHOWN	DWN. BY: <u>CLS</u>
JOB NO. <u>C0011-005</u>	DWG. NO. <u>---</u>
SUBMITTED: <u>---</u>	SURV. BY: <u>---</u>
	<p>THIS SEAL WAS AUTHORIZED BY STEVE E. DUNCAN, 83252 ON 06/03/2009</p>
<p>SHEET NO. SD-3 OF 3</p>	



Planting Plan
Carver School Entrance

City Project No. 350-D8-0828
MLK Sidewalk and Streetscape Phase 1 & 2
Bryan
77803

Sheet Date: 05/20/09
LFS 9.033.11

Sheet Title:
LS1
Sheet No.:
1 OF 1
Drawn By: Project Manager
JC AK

General Notes


01. All Plant Material shall be pruned / shaped as per Landscape Architect after installation to remove any broken or damaged branches and to give uniformity of shape.
02. All Plant Material must be approved by the Landscape Architect before installation.
03. Verify all quantities before installation.
04. Broken pieces of sod (smaller than 8" square) are not acceptable.
05. All Crape Myrtle Trees are to be pruned up to expose 4' clear trunk(s).
06. Landscape Contractor is responsible for clearing any dirt or mud from public roadway. Landscape Contractor is also responsible for keeping the site clean during construction and plant installation.
07. All proposed "New Canopy Trees" shall be containerized.
08. An automatic irrigation system will cover the entire landscaped areas.
09. Bedding Soil (flowerbeds) shall be prepared to a depth of 8 inches and consist of 40% Sandy Loam Topsoil, 60% Black Humus.
10. All flowerbeds shall be top dressed with a 3" layer of Black Humus or equal.
11. Install 3' diameter mulch rings (3" thick) around all trees (canopy and non-canopy) which appear in lawn areas.
12. All plant material is to be guaranteed for 1 full year.
13. Erosion control is required as needed and clean-up is included.
14. See Site Plan for topographic information, existing and proposed utilities, easements, adjacent land uses, existing development and roadways.

Indian Hawthorne (12)
Raphiolepis indica
12-5 gallon 30" height minimum

New Gold Lantana (20)
Lantana x hybrida 'New Gold'
20-1 gallon full stringers, plant 36" apart

Existing Sign
Verify location


Steel Edging Border
No sharp corners to be exposed
FOR BED PREPARATION AND PLANTING
SEE DETAIL 02-LS1



01

BED LAYOUT

SCALE: 1/8" = 1'-0"
VERIFY ALL DIMENSIONS



SHRUB PLANT MATERIAL, (TYP.)
EVENLY DISTRIBUTE THE SPECIFIED QUANTITY OF
PLANTS WITHIN EACH DESIGNATED AREA.
MAINTAIN EDGE AND SEPARATION DISTANCES
BETWEEN PLANT TYPES.

3" MULCH LAYER
NO GEOTEXTILE WEED BARRIER FABRIC
PLANTING IN BEDS.

PREPARED BEDDING SOIL BACKFILL TYP.
1. FULLY REMOVE NATIVE SOIL TO THE SIZE OF CONTAINER.
2. FULLY REMOVE ALL CONSTRUCTION DEBRIS, TRASH, ROCKS
AND ANY OTHER MATERIAL GREATER THAN 2" IN DIAMETER.
3. INSTALL PREMIXED SOIL CONTAINING 50% NATIVE SOIL,
25% HUMUS AND 25% SAND.
4. DIG PLANTING HOLE WIDTH 12" LARGER THAN ROOTBALL ON
ALL SIDES.
5. SCARIFY ROOT BALL.
6. ROOT FLARE SHALL BE EXPOSED.

MAKE SURE THAT PLANT ROOT BALL IS FULLY PLANTED
TO DEPTH OF CONTAINER IN PREPARED PLANTING MIX.
DO NOT PLANT GROUNDCOVER IN MULCH LAYER ONLY.

NATIVE SOIL


NOTE:

1. CONTAINER GROWN PLANTS ONLY.
2. REMOVE CONTAINERS FROM PLANTS BEFORE
INSTALLING.
3. PLACE PLANTS IN PREPARED BED AS SHOWN.
4. IRRIGATION FOR ALL BEDS THROUGH
LANDSCAPE TO BE DRIP IRRIGATION

02


PLANTER DETAIL

SCALE: NTS
VERIFY ALL DIMENSIONS




24" LAY DOWN
GUTTER SECTION

ST1-00




TYPICAL
RIBBON CURB

ST1-03




TYPICAL COMBINED
CURB & GUTTER SECTION

ST1-01




TYPICAL COMBINED
SPILL CURB

ST1-04




DOWELLED IN CURBS
DETAIL

ST1-02




TYPICAL WEEPHOLE CURB

ST1-05




ALLEY PAVING

ST1-06




SECTION A-A
WITH LAYDOWN CURB




RESIDENTIAL DRIVEWAY

ST2-00




TYPICAL DRIVEWAY ENTRANCE
WITH CULVERT

ST2-02




SECTION A-A
SLOPING AWAY FROM INTERSECTION




TYPICAL STREET CONCRETE APRON

ST2-01




COMMERCIAL DRIVEWAY

ST2-03




TYPE \"D\"
LONGITUDINAL JOINT

LONGITUDINAL JOINTS SHALL BE REQUIRED ONLY ON THE CENTERLINE OF THE PAVEMENT & IN INTERSECTIONS AS DETAILED




TANGENT SECTIONS
TYPICAL JOINT & REINFORCEMENT LAYOUT
FOR CONCRETE PAVEMENT

METAL KEY WAY PLATE



TYPE \"B\"
CONTRACTION JOINT


TRANSVERSE JOINTS SHALL BE SPACED 15' CENTER TO CENTER



TYPICAL JOINT LAYOUT AT
CONCRETE INTERSECTION


ST3-00

GENERAL NOTES:
ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOCK SODDED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOCK SOD WILL BE REQUIRED. BARED AREAS SHALL BE SEEDED OR SODDED WITHIN 14 CALENDAR DAYS OF LAST DISTURBANCE.
APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.
ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.




OPEN CUT
GRAVEL STREET

ST4-00




OPEN CUT SEAL COAT/
OVERLAY STREET

ST4-01




OPEN CUT CONCRETE STREET

ST4-02




TYPICAL RURAL ROAD RIBBON CURB SECTION

ST4-03




TYPICAL STREET SECTION

ST4-05



TYPICAL RURAL ROAD SECTION

ST4-04




TYPICAL STREET SECTION


ST4-06

REVISIONS:

BRYAN - COLLEGE STATION
STANDARD STREET DETAILS




DRAWN BY: C.L.M.
DATE: 01-01-08
SCALE: N T S
APPROVED: W.P.K.
FIGURE:
ST
SHEET 1 OF 1



SIDEWALK SLOPE REQUIREMENTS

SW1-00



TYPICAL PEDESTRIAN GUARDRAIL

SW1-01


GENERAL NOTES:

ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOCK SODED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOCK SOO WILL BE REQUIRED. BARED AREAS SHALL BE SEEDED OR SOODED WITHIN 14 CALENDAR DAYS OF LAST DISTURBANCE.


APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.

ALL EROSION CONTROL MEASURES SHOULD BE CLEARED OF SILT AFTER EVERY RAIN.


- NOTES:**
- SIDEWALK PLACEMENT SHALL BE IN ACCORDANCE WITH B/C/S UNIFIED DESIGN GUIDELINES.
 - FRESHLIGHT BROOM FINISH JOINTS TO BE TOOLED 1" DEEP AT AN INTERVAL EQUAL TO THE SIDEWALK WIDTH. EXPANSION JOINTS @ 40' O.C. CONTRACTION JOINTS @ 4' O.C.
 - DOWEL IN AND TIE TO ANY CONCRETE STRUCTURE ADJACENT TO SIDEWALK (DRIVEWAY, INLET BOX, CURB, JUNCTION BOX, ETC.) WITH #3 X 12" BARS @ 12" O.C. OR #4 X 12" BARS @ 18" O.C.
 - COMPACTION: COMPACTED SUBGRADE MATERIAL COMPACTED TO A DENSITY AT LEAST 98% OF MAXIMUM DRY DENSITY AS DETERMINED BY PROCTOR COMPACTION TEST ASTM D698 (STANDARD) AND SHALL BE 0-4% WET OF THE OPTIMUM MOISTURE CONTENT
 - A MINIMUM CLEAR PEDESTRIAN WIDTH AS DEFINED BY T&S AND ADA SHALL BE PROVIDED FOR ENTIRE LENGTH OF SIDEWALK.



SIDEWALK EXPANSION & CONSTRUCTION JOINT




SIDEWALK CONTRACTION JOINT




SIDEWALK PAVER SECTION


CONCRETE SIDEWALK



ALONG LOCAL STREETS




ALONG MINOR COLLECTORS AND LARGER




ALONG MINOR COLLECTORS AND LARGER

SW1-02




TYPICAL PLACEMENT OF DETECTABLE WARNING SURFACE ON LANDING AT STREET EDGE

SW2-00




TYPICAL PLACEMENT OF DETECTABLE WARNING SURFACE ON SLOPING RAMP RUN

SW2-01



TYPICAL AMBULATORY RAMP W/ FLARED WINGS

SW2-02



DETECTABLE WARNING PAVER

TRUNCATED DOME PATTERN CURB RAMP


DETECTABLE WARNING PAVER

- GENERAL NOTES FOR DETECTABLE WARNINGS**
- CURB RAMPS MUST CONTAIN A DETECTABLE WARNING SURFACE THAT CONSISTS OF RAISED TRUNCATED DOMES COMPLYING WITH SECTION 4.29 OF THE TEXAS ACCESSIBILITY STANDARDS (TAS). THE SURFACE MUST CONTRAST VISUALLY WITH ADJACING SURFACES, INCLUDING SIDE FLARES, FURNISH DARK BROWN OR DARK RED DETECTABLE WARNING SURFACE ADJACENT TO UNCOLORED CONCRETE, UNLESS SPECIFIED ELSEWHERE IN THE PLANS.
 - DETECTABLE WARNING SURFACES MUST BE SLIP RESISTANT AND NOT ALLOW WATER TO ACCUMULATE.
 - ALIGN TRUNCATED DOMES IN THE DIRECTION OF PEDESTRIAN TRAVEL WHEN ENTERING THE STREET.
 - SHADED AREAS ON SHEETS 3 AND 4 INDICATE THE APPROXIMATE LOCATION FOR THE DETECTABLE WARNING SURFACE FOR EACH CURB RAMP TYPE.
 - DETECTABLE WARNING SURFACES SHALL BE A MINIMUM OF 24" IN DEPTH IN THE DIRECTION OF PEDESTRIAN TRAVEL, AND EXTEND THE FULL WIDTH OF THE CURB RAMP OR LANDINGS WHERE THE PEDESTRIAN ACCESS ROUTE ENTERS THE STREET.
 - DETECTABLE WARNING SURFACES SHALL BE LOCATED SO THAT THE EDGE NEAREST THE CURB LINE IS A MINIMUM OF 6" AND A MAXIMUM OF 10" FROM THE EXTENSION OF THE FACE OF CURB. DETECTABLE WARNING SURFACES MAY BE CURVED ALONG THE CORNER RADIUS.
 - ACCEPTABLE PAVER MATERIAL SHALL BE CLAY, VITRIFIED POLYMER COMPOSITE, PRECAST POLYMER CONCRETE, AND CONCRETE.
- PEDESTRIAN FACILITIES GENERAL NOTES**
- ALL SLOPES ARE MAXIMUM ALLOWABLE. THE LEAST POSSIBLE SLOPE THAT WILL STILL DRAIN PROPERLY SHOULD BE USED. ADJUST CURB RAMP LENGTH OR GRADE OF APPROACH SIDEWALKS AS DIRECTED.
 - LANDINGS SHALL BE A 5' X 5' MINIMUM WITH A MAXIMUM 2% SLOPE IN ANY DIRECTION.
 - MANEUVERING SPACE AT THE BOTTOM OF CURB RAMPS SHALL BE A MINIMUM OF 4' X 4' WHOLLY CONTAINED WITHIN THE CROSSWALK AND WHOLLY OUTSIDE THE PARALLEL VEHICULAR TRAVEL PATH.
 - MAXIMUM ALLOWABLE CROSS SLOPE ON SIDEWALK AND CURB RAMP IS 2%.
 - CURB RAMPS WITH RETURNED CURBS MAY BE USED ONLY WHERE PEDESTRIANS WOULD NOT NORMALLY WALK ACCESS THE RAMP. EITHER BECAUSE THE ADJACENT SURFACE IS PLANTING OR OTHER NON-WALKING SURFACE OR BECAUSE THE SIDE APPROACH IS SUBSTANTIALLY OBSTRUCTED. OTHERWISE, PROVIDE FLARED SIDES.
 - ADDITIONAL INFORMATION ON CURB RAMP LOCATION, DESIGN, LIGHT REFLECTIVE VALUE AND TEXTURE MAY BE FOUND IN THE CURRENT EDITION OF THE TEXAS ACCESSIBILITY STANDARDS (TAS) AND 16 TAC §68.102.
 - TO SERVE AS A PEDESTRIAN REFUGE AREA, THE MEDIAN SHOULD BE A MINIMUM OF 5' WIDE. MEDIANS SHOULD BE DESIGNED TO PROVIDE ACCESSIBLE PASSAGE OVER OR THROUGH THEM.
 - CROSSWALK DIMENSIONS, CROSSWALK MARKINGS AND STOP BAR LOCATIONS SHALL BE AS SHOWN ELSEWHERE IN THE PLANS. AT INTERSECTIONS WHERE CROSSWALK MARKINGS ARE NOT REQUIRED, CURB RAMPS SHALL BE ALIGNED WITH THEORETICAL CROSSWALKS, OR AS DIRECTED BY THE ENGINEER.
 - EXISTING FEATURES THAT COMPLY WITH TAS MAY REMAIN IN PLACE UNLESS OTHERWISE SHOWN ON THE PLANS.
 - HANDRAILS ARE NOT REQUIRED ON CURB RAMPS, PROVIDE CURB RAMPS WHEREVER ON ACCESSIBLE ROUTE CROSSES (PENETRATES) A CURB.
 - SEPARATE CURB RAMP AND LANDINGS FROM ADJACENT SIDEWALK AND ANY OTHER ELEMENTS WITH PRECAST OR BUILTUP JOINT OF 3/4" UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 - PROVIDE A SMOOTH TRANSITION WHERE THE CURB RAMPS CONNECT TO THE STREET.
 - FLARE SLOPE SHALL NOT EXCEED 10% MEASURED ALONG CURB LINE.

GENERAL NOTES (PAVERS)


FURNISH DETECTABLE WARNING PAVER UNITS MEETING ALL REQUIREMENTS OF ASTM C-926, C-33. LAY IN A TWO BY TWO UNIT BASKET WEAVE PATTERN OR AS DIRECTED.

LAY FULL-SIZE UNITS FIRST FOLLOWED BY CLOSURE UNITS CONSISTING OF AT LEAST 25 PERCENT OF A FULL UNIT. CUT DETECTABLE WARNING PAVER UNITS USING A POWER SAW.




SECTION A-A

SW2-03




8' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION

SW3-00




5' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION

SW3-01




6' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION

SW3-02




8' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION

SW3-03




5' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION

SW3-04




6' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION

SW3-05




8' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION & DRIVES

SW4-00



6' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION & DRIVES


SW4-01



5' SIDEWALK AMBULATORY RAMP AT STREET INTERSECTION & DRIVES




SW4-02

**BRYAN - COLLEGE STATION
STANDARD SIDEWALK DETAILS**



CITY OF BRYAN
The Good Life, Texas Style.

FIGURE:
SW
SHEET 1 OF 1




REVISIONS:

BRYAN - COLLEGE STATION
STANDARD DRAINAGE DETAILS



DRAWN BY: C. L. M.
DATE: 01-01-08
SCALE: N T S
APPROVED: W. P. K.



BRYAN - COLLEGE STATION
STANDARD STORM WATER
POLLUTION PREVENTION DETAILS




DRAWN BY: C.L.M.
DATE: 01-01-08
SCALE: N T S
APPROVED: W. P. K.

FILE: MB-06(1).dgn

LEVELS DISPLAYED															
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32
33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	


DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.



FOR SUPPORT/FOUNDATION
DETAILS SEE SHEET 3 OF 3


INDEX OF MAILBOX DETAIL SHEETS

- | | |
|--------|------------------------------------|
| 1 of 3 | MAILBOX MOUNTING AND SPACING |
| 2 of 3 | MAILBOX BRACKET CONNECTING DETAILS |
| 3 of 3 | MAILBOX SUPPORT / FOUNDATION |



* Type 2 object marker in accordance with standard D&OM (1) or tube type post wrapped with 12" Sheeting Fluorescent yellow in accordance with DMS 8600 for tubular post needed to produce a smooth wrap around tube, DHT 161812.

MULTIPLE MAILBOX MOUNT



NEWSPAPER RECEPTACLE

A light weight receptacle for newspaper delivery should be attached to the post of single and double mailboxes if the receptacle:

- Does not touch the mailbox.
- Does not present a hazard to traffic or delivery of the mail.
- Does not extend beyond the front of the mailbox.
- Does not display advertising, except the publication title.

FOR SUPPORT/FOUNDATION
DETAILS SEE SHEET 3 OF 3

Note on DHT Number

See Table of Applicable DHT Numbers on sheet 3 of 3 for DHT description.

REVISIONS
04/03/06: Added New Multiply Mount, DHT: 164116.
04/03/06: Added general note numbers 6 & 7.
Sheet & title block renumbered.
11/14/06: Deleted sheet 4

08/02/06: Added Maximum weight for typical mailbox size.

Standard Plans
Texas Department of Transportation
Maintenance Division

MAILBOX MOUNTING AND SPACING

MB-06(1)

Sheet 1 of 3


FILE:	MB06(1).DGN	DW:	JEO	CK:	LJB	DW:	JEO	CK:	JG	NEG:	
© TxDOT NOVEMBER 2006		DIST	FED REG	FEDERAL AID PROJECT		SHEET					
6		COUNTY		CONTROL		SECT		JOB		HIGHWAY	

Mailboxes shall be made of light weight sheet metal or light weight plastic. Heavy steel, cast iron or decorative mailboxes shall not be used on the state highway system.


TYPICAL MAILBOX SIZE				LIGHT WEIGHT MATERIAL	
				SHEET METAL	**PLASTIC
SIZE	LENGTH	WIDTH	HEIGHT	MAXIMUM WEIGHT	
	INCHES			POUNDS	
SMALL	19 1/2	6	7	5	5
MEDIUM	22 1/2	8	11 1/2	7	7
LARGE	23 1/2*	11 1/2*	13 1/2*	10	10

* Maximum allowed dimensions for mailbox
** Excluding Molded Plastic on 4 X 4 Post

MAILBOX SIZES



MULTIPLE MAILBOX PLACEMENT




SINGLE & DOUBLE MAILBOX PLACEMENT

FILE: MB-06-(1).dgn

LEVELS DISPLAYED															
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32
33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	


DISCLAIMER:

The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




DHT 162323

For use with galvanized thinwall steel posts DHT # 143426 or powder-coated thinwall steel post DHT # 162911.



DHT 161443

For use with RCR post DHT # 161442 or galvanized thinwall steel post DHT # 143426 or powder-coated thinwall steel post. DHT # 162911.



DHT #3789


Used for mounting two Mailboxes on the same post.

Note on DHT Number

See Table of Applicable DHT Numbers on sheet 3 of 3 for DHT description and unit of measure.


HARDWARE AT TXDOT REGIONAL WAREHOUSES

Brackets and adapter plate shown in this section should be available to the Contractor when stated elsewhere in plans or specifications.



DHT 148939


Mailbox Bracket



DHT 148938


Used for extending 6" wide bracket to attach larger mailboxes.

Bracket Extension




DHT 159489

Part "A" Angle Bracket Connector



DHT 159490

Part "B" Angle Bracket Connector



DHT 2917

Angle Bracket For Temporary Mailbox


Standard Plans
Texas Department of Transportation
Maintenance Division

**MAILBOX BRACKET
CONNECTING DETAILS**

MB-06(1)


Sheet 2 of 3

FILE: MB06(1).DGN	DN: LJB	CK: JEO	DW:	CK: JG	NEG:
© TxDOT NOVEMBER 2006	DIST	FED REG	FEDERAL AID PROJECT		SHEET
02/02/05	REVISIONS		6		
06/08/05: Added general note numbers 6 & 7, Sheet & title block renumbered, 11/14/05: Deleted sheet4.			COUNTY	CONTROL	SECT
				JOB	HIGHWAY




For bolt sizes see details below for "SMALL MAILBOX" and "MEDIUM AND LARGE MAILBOXES"

SINGLE MAILBOX CONNECTION




DOUBLE MAILBOX CONNECTION

(Not permitted for Large Mailboxes)




MULTIPLE MAILBOX CONNECTION



**WELDED SINGLE MAILBOX
BRACKET CONNECTION**

To be used with 2 3/8" OD RR or thinwall Steel posts.




**WELDED DOUBLE MAILBOX
BRACKET CONNECTION WITH
ADAPTER PLATE**


To be used with thinwall Steel posts. Not to be used with RR posts.

GENERAL NOTES


- Connecting hardware detailed on this sheet is for the hardware that the Department stocks at the Regional Warehouses. This hardware is available to the contractor only when so stated elsewhere in the plans or specification.
- Hardware for mounting mailboxes to the support/foundation furnished by industry should be used when shown on the Maintenance Divisions "Approved Products List." Only mailbox hardware that have been crash tested in accordance with NCHRP Report 350, will be on the approved list.
- Hardware furnished by industry shall be erected in accordance with the manufacturer's recommendation.
- Bracket and bracket extension shall be constructed of 14 gauge galvanized steel sheet metal.
- The angles, brackets and adapter plates shall be constructed of 12 gauge galvanized steel sheet metal.
- Items with evidence of damage to the galvanized coating or wet storage stains (white rust) will not be accepted.



SMALL MAILBOX



MEDIUM AND LARGE MAILBOXES



- Bracket to mailbox attachment:
6 - 1/4" Dia. x 3/4" bolt w/2 flat washers and nut per each bolt.
- Bracket to bracket extension attachment:
2 - 1/4" Dia. x 3/4" carriage bolt w/ flat washer, lock washer and nut per bolt (4 bolts required if 2 bracket extensions are used).
- Angle to bracket attachment:
2 - 3/8" Dia. x 3/4" bolt w/2 flat washers, lock washer and nut per each bolt.
- Angle to mailbox support attachment:
2 - 3/8" Dia. x 2 1/2" bolt w/2 flat washers, lock washer, and nut per each bolt.
- Medium size mailboxes - one extension bracket
Large size mailboxes - two extension brackets

[illegible]

TABLE OF APPLICABLE DHT NUMBERS	
DHT	DESCRIPTION
NUMBER	
FOUNDATIONS	
46625	WEDGE FOR V-WING SOCKET FOR TYPE 1 FOUNDATION
149340	V-WING SOCKET FOR TYPE 1 FOUNDATION
143433	WEDGE FOR TYPE 2 FOUNDATION
143434	ANCHOR FOR TYPE 2 FOUNDATION
160891	SOCKET FOR TYPE 4 FOUNDATION
160892	WEDGE FOR TYPE 4 FOUNDATION
POSTS	
4289	WINGED CHANNEL MAILBOX POST
149339	MULTIPLE MAILBOX POST (GALVANIZED TUBING)
164116	MULTIPLE MAILBOX POST (WHITE COATED)
161442	RECYCLED RUBBER POST. FOR SMALL MAILBOX ONLY
143426	THIN-WALL GALVANIZED STEEL TUBE 2.375" OUTER DIAMETER
162911	THINWALL WHITE STEEL TUBE 2.375" OUTER DIAMETER
REFLECTIVE SHEETING	
161812	REFLECTIVE SHEETING FOR EMERGENCY LOCATION NUMBER PANEL
CONNECTING HARDWARE	
2917	ANGLE BRACKET USED FOR TEMPORARY MAILBOX SUPPORT
3789	PLATE FOR DOUBLE MOUNTING OF MAILBOXES
148939	BRACKET FOR ATTACHING SMALL OR MEDIUM SIZE MAIL BOX
148938	EXTENDER TO BRACKET FOR ATTACHING LARGE MAILBOX
159490	ANGLE BRACKET PART B
159489	ANGLE BRACKET PART A
162323	BRACKET FOR DOUBLE MOUNTING OF MAILBOXES ON THINWALL STEEL POST, GALVANIZED OR POWDERCOATED.
161443	BRACKET FOR ATTACHING MAILBOX TO RECYCLED RUBBER POST AND TO MULTIPLE WHITE MAILBOX POST
DOUBLE AND LARGE MAILBOXES MUST BE ON STEEL POST.	

- ### GENERAL NOTES
1. Erect post plumb or vertical.
 2. When galvanized part is required galvanize in accordance with Item 445.
 3. Type 1, 2, 3, or 4 supports or foundation can be used for single or double mailbox installations. The RCR post should be used only for a single installation with a small mailbox. The Type 5 support/foundation is used for the single molded plastic mailbox. The Type 4 support/foundation is used for the 2.375" O.D. RCR post, thin wall steel post, and white multiple mailbox post.
 4. The Type 1 support/foundation can be used for a multiple mailbox mount. DHT 149339
 5. The Type 4 support should be used with thin wall steel pipe for the medium, large and double mailbox installations.
 6. Use a concrete footing as shown or when directed. Concrete footing will be required when soils do not hold the support/foundations in a stable condition.
 7. A 2.375" O.D. galvanized thin wall posts can be used for Ty 1, 2 & 4.
 8. When specified elsewhere in the plans, a 2.375% O.D. galvanized thin wall powder coated white post DHT-162911 should be used for the medium, large, and double mailbox installations.

 *Texas Department of Transportation*
Maintenance Division

MAILBOX SUPPORT/ FOUNDATION

Sheet 3 of 3 **MB-06(1)**

FILE: MB06(1).DGN	DN: JEO	CK: LJB	DN: JEO	CK: JG	NEG:
① X:DOT NOVEMBER 2006	DIST	FED REG	FEDERAL AID PROJECT		SHEET
02/02/05 REVISIONS	6				
06/08/05: Added general note	COUNTY	CONTROL		SECT	JOB HIGHWAY
numbers 6 & 7. Sheet & title block					
revised. 11/14/05 Deleted sheet 8,					
08/03/06: Added DHT table, Mailbox					
descriptor: pldive codes and dht items.					

*HDTP: High density thermoplastic polyesters